



BASSETLAW HOSPITAL, PHASE 1

STRUCTURAL INSPECTION REPORT

22nd October 2021

RAAC PLANK INSPECTION

AJP Ref: 221-007

PREPARED BY MIKE CARR



RAAC PLANK INSPECTION

Client Ref: 221-007

DONCASTER AND BASSETLAW TEACHING HOSPITALS NHS FOUNDATION TRUST



Doncaster and Bassetlaw Teaching Hospitals NHS Foundation Trust

Record of Approval	Originator:	Approved:	Date:
	M.Carr - Senior Structural Engineer	P. Bryan - Director	22.10.2021

Version	Author:	Change Description:	
01	Mike Carr - Senior Structural Engineer	Initial issue for trust comments	22.10.2021

Contents

1. INTRODUCTION	3
2. REINFORCED AUTOCLAVED AERATED CONCRETE.....	3
3. STRUCTURAL ASSESSMENT METHOD	4
4. BUILDING INTRODUCTION	4
5. RAAC SUMMARY AND DEFECTS IDENTIFIED	4
6. RECOMMENDATIONS	14
<i>6.1 Option 1 – Retain RAAC planks, repair leaks, and undertake ongoing inspections</i>	<i>14</i>
<i>6.2. Option 2 – Remove RAAC planks and replace roof with suitable construction.....</i>	<i>14</i>
7. SUMMARY OF RECOMMENDATIONS	15
APPENDICES	15

1. INTRODUCTION

The Alan Johnston Partnership LTD have been appointed by *Doncaster and Bassetlaw Teaching Hospitals NHS Foundation Trust* to undertake a structural review of several buildings within the hospital estate where RAAC planks have been identified in their construction. This report includes the building known as “Phase 1” or “building 43”, which houses the Emergency Department (ED), operating theatres and plant rooms. It should be noted that AJP conducted a previous survey in February 2021 simply to identify the construction and any immediate defects.



FIGURE 1 - BUILDING LOCATION WITHIN THE SITE

The area highlighted above has a roof constructed from Reinforced Autoclaved Aerated Concrete (RAAC), a construction which has been identified as problematic in certain circumstances and is subject to a checking instruction from the NHSI. This report details the findings of the inspection carried out on the 15th of October, and outlines various recommendations in managing the risks identified.

2. REINFORCED AUTOCLAVED AERATED CONCRETE

Autoclaved aerated concrete is different from normal dense concrete. There are no coarse aggregates and the concrete is filled with chemically induced gas bubbles to reduce its weight. It is relatively weak and was used widely in the 1960's – 1980's for roof construction. Several instances of sudden collapse have been attributed to RAAC, which has a useful lifespan estimated to be around 30 years.

In late 2019, the Local Government Association (LGA) drew attention to potential structural issues surrounding RAAC roof plank and made recommendations relating to maintenance and inspection regimes. This was followed by a publication by the Standing Committee on Structural Safety (SCOSS) which highlights the findings of testing/case studies.

The common causes of failure were identified by the report are as follows:

- Incorrect/insufficient cover to reinforcement
- Creep (continued deflection over time) due to a low stiffness
- Insufficient anchorage of reinforcement at support points
- Water ingress and the associated reinforcement corrosion, particularly at support points
- Failed waterproofing membranes
- Insufficient bearing or reinforcement at support points

The main manufacturer of the planks, Siporex, published technical literature in 1972 which lays out the principles to be adopted when using RAAC planks in roof construction.

Failures can be anticipated if the planks are cracking or bowing significantly. Failures can also occur suddenly and without warning if defects are hidden beyond the observable surface. Refer to the illustration below.




FIGURE 2 – INDICATIONS OF ANTICIPATED FAILURES (LEFT) AND EXAMPLES OF SUDDEN FAILURES (RIGHT)

3. STRUCTURAL ASSESSMENT METHOD

Inspections were undertaken during normal daytime operation hours with assistance from estates staff. The weather was dry, but rain had clearly fallen in the previous days.

The inspection was visual, and allowed the condition of each roof plank to be assessed from the underside. The following signs of deterioration/defects were checked for:

- Excessive deflection (typically causing visible bowing)
- Signs of water ingress or corrosion of reinforcement
- Insufficient end bearing (less than 45mm)
- Cracking
- Spalling
- Discolouration/staining
- Non-standard plank sizes
- Penetrations or cuts that may weaken the planks
- Ponding of water at roof level

4. BUILDING INTRODUCTION

Based on a desktop study of historical maps, phase 1 appears to have been constructed circa 1980. The building is primarily a three-storey loadbearing masonry construction, with elements of steel framing and in-situ concrete. RAAC roof planks span onto steel trusses to form a flat roof, which is accessible by means of a permanent ladder.

The roof void houses an abundance of services/ducts which connect to the operating theatres below. The majority of the ducts are suspended from the RAAC planks above using drilled fixings. A small area of the roof void is double height to facilitate incoming services from an adjacent taller section of the building. The roof construction over this double height area is of a lightweight metal deck and steel beam/column arrangement.

5. RAAC SUMMARY AND DEFECTS IDENTIFIED

Refer to AJP drg BLH-AJP-ZZ-RF-DR_S-0001 in the appendix. 267 no. RAAC planks were identified in the building generally measuring 600mm in width, and 6" (152mm) in depth based on site measurements. A small number of planks were measured between 250mm and 450mm in width. Although several planks were partially obscured by ducts and services, AJP were able to uniquely identify each plank within the roof void. The external roof condition was inspected from above; build-up over the planks is likely to contain insulation topped with waterproof finishes.

A variety of general defects were identified, as follows:

- Severe water damaged ply boarding forming the floor due to water ingress, this occurs immediately adjacent to the steel plant room door (photo 1)
- Saw cut holes, plank 15 (photo 2)
- Loose and structurally inadequate barriers preventing access onto ventilation units, occurs above theatres 6, 5 and 4 (photo 3)

- Roughly cut units exposing reinforcement, planks 102, 111, 143, 166, 199, 222 and 245 (photo 4)
- Untreated exposed reinforcement, plank 15 (photo 5)
- Loosely fitting and missing holding down clips (photo 6)
- Long term ponding of water at roof level (photo 7A and 7B)
- Water ingress through roof build-up, plank staining and moderate floor damage particularly above theatre 4 (photo 8A and 8B)
- Unprotected falls from height, occurs where roof ladder is positioned (photo 9)

Generally, bearing lengths appeared to be in excess of 80mm and reinforcement cover was found to be 20mm to 30mm. Main tension reinforcement in the bottom of each plank was consistently found to be at 75mm centres. Refer to photo 10 for a visual aid. Span/depth ratios are around Span/22. None of these geometric values are cause for concern.



PHOTO 1 – SEVERE WATER DAMAGED PLY BOARDING




PHOTO 2 – RAAC PANEL CUT AT SUPPORT LOCATION



PHOTO 3 – LOOSE HANDRAILS



PHOTO 4 – ROUGHLY CUT RAAC PLANK



PHOTO 5 – CORROSION OF UNPROTECTED REINFORCEMENT



PHOTO 6 – MISSING PLANK CLIPS FOR HOLDING DOWN



PHOTO 7A – PONDING, PHOTOGRAPH FEBRUARY 2021



PHOTO 7B – PONDING, PHOTOGRAPH OCTOBER 2021



PHOTO 8A – WATER INGRESS AND STAINING OF PLANKS



PHOTO 8B – MODERATE WATER DAMAGE BELOW WATER INGRESS LOCATIONS




PHOTO 9 – UNPROTECTED FALLS FROM HEIGHT




PHOTO 10 – REINFORCEMENT ARRANGEMENT

6. RECOMMENDATIONS

Based on the building age and survey findings, it is suggested that the RAAC planks are nearing the end of their useful life (50 years). Although the planks appear to be in reasonable condition and are not displaying any indications of overstress (cracking or deflecting) it is not possible to identify defects which lie beneath the observable surfaces, and a very small number of recent failures in the UK have occurred suddenly without warning. It is recommended that plank 15 is re-supported to account for the significant cut which appears to coincide with reinforcement. This may involve a timber beam arrangement fixed between the trusses. AJP are to advise further on the re-support detail upon receipt of NHS trust comments. Any visibly exposed unpainted/untreated reinforcement should be thoroughly wire brushed and protected. The damaged ply flooring has a very reduced lifespan and it should be replaced at the earliest suitable opportunity.

6.1 Option 1 – Retain RAAC planks, repair leaks, and undertake ongoing inspections

As part of the works, it is recommended that the trust appoint a specialist subcontractor to undertake GPR ferro-scans from above, thereby allowing AJP to verify the reinforcement content of the planks in all instances and identify any planks which may be more susceptible to sudden failure. Referring to the previous AJP report, residual imposed load capacity of the planks was identified as 1.25kN/m^2 (allowing for 1kN/m^2 finishes + services). The subcontractor should take account of this in their risk assessment/method statement.

It is recommended the gullies at roof level are inspected by estates during periods of heavy rain to ensure they are draining freely. Several gullies were missing caps which prevent blockages, these should be re-fitted if possible. Consideration should be given to identifying any surface damage where water is able to penetrate, and sealing with a synthetic rubber patching system. Unless the roof is re-surfaced with tapered insulation or similar to achieve a minimum fall it will be challenging to fully address the standing water issue.

Given the condition of the planks, and relatively short spans, AJP suggest that ongoing inspections should be undertaken annually. Frequency of inspection may change if signs of deterioration appear in the coming years, or if industry guidance is updated.

6.2. Option 2 – Remove RAAC planks and replace roof with suitable construction

Eradication of the planks will eliminate the need for any future inspections. It is unlikely that this option will be feasible due to the criticality of the theatres below. Following the removal of the existing roof finishes, an appropriate method of removing the RAAC planks from the roof will need to be devised and developed with a suitably experienced demolition contractor. Temporary stability of the walls will need consideration, as they may rely on the planks to resist wind loading. All ductwork supported by the RAAC planks will need removing or re-supporting. Based on the roof span, it is likely that a timber roof with insulation laid to falls and waterproofing will be an economical solution.

7. SUMMARY OF RECOMMENDATIONS

TABLE 1: BENEFITS AND DRAWBACKS FOR OPTIONS 1 AND 2

	Benefits	Drawbacks
Option 1 – Retain RAAC	Small amounts of immediate term works are required. Minimal/no impact on hospital functionality.	RAAC remains on site and is an ongoing risk requiring routine inspection annually. Additional GPR ferro-scanning works required. Roof ponding will not be remediated without re-roofing works.
Option 2 – Replace roof	RAAC risk entirely eradicated, modern construction will improve overall building performance. Roof ponding will be addressed.	Full de-cant of the theatres will be required as the works take place. ED access will be temporarily affected. Logistically challenging to remove the planks, external walls may need temporary support

In addition to the above options, the items below confirm further recommendations. Those in green should be risk assessed by the trust, whereas those in red are considered by AJP as essential.

- Demarcation of areas with loose barriers (see photo 3)
- Installation of a barrier to prevent fall from height (see photo 9)
- Patch repair of roof leaks where ponding has occurred if planks retained
- Refit missing gulley caps at roof level if planks retained
- Inspect the gullies during heavy rain to check they drain freely if planks retained
- Re-support of plank 15 if planks are to be retained
- Treatment and protection of exposed/corroding reinforcement if planks retained
- GPR ferro-scanning from above if planks are to be retained
- Repair of damaged ply flooring (see photo 1 and 8B)


AJP suggest that the following course of action is suitable:

1. NHS Trust to evaluate the contents of this report and provide any relevant feedback
2. AJP to develop proposals in full, including drawings and specifications
3. NHS Trust to approach suitably experienced contractors and sub consultants where necessary capable of undertaking the works
4. AJP to work with contractor/UET to develop a suitable method of works
5. Works to be completed at a suitable time


APPENDICES

Appendix A – AJP drg BLH-AJP-ZZ-RF-DR-S-0001, overall layout of the building showing RAAC planks


A+E ENTRANCE AT LEVEL 0




PLAN AT RAAC PANEL LEVEL
(SCALE 1:50)



TYPICAL RAAC PLANK SECTION
(SCALE 1:10)




SECTION A-A
(SCALE 1:50)



SECTION B-B
(SCALE 1:25)

PLANK SCHEDULE				PLANK SCHEDULE				PLANK SCHEDULE				PLANK SCHEDULE				PLANK SCHEDULE			
Unit No.	Width (mm)	Depth (mm)		Unit No.	Width (mm)	Depth (mm)		Unit No.	Width (mm)	Depth (mm)		Unit No.	Width (mm)	Depth (mm)		Unit No.	Width (mm)	Depth (mm)	
1	600	150		51	600	150		101	450	150		151	600	150		201	600	150	
2	600	150		52	600	150		102	250	150		152	600	150		202	600	150	
3	600	150		53	600	150		103	600	150		153	600	150		203	600	150	
4	600	150		54	600	150		104	600	150		154	600	150		204	600	150	
5	600	150		55	600	150		105	600	150		155	600	150		205	300	150	
6	600	150		56	450	150		106	600	150		156	600	150		206	600	150	
7	600	150		57	600	150		107	600	150		157	600	150		207	600	150	
8	600	150		58	450	150		108	300	150		158	600	150		208	600	150	
9	600	150		59	450	150		109	300	150		159	600	150		209	600	150	
10	600	150		60	600	150		110	600	150		160	600	150		210	600	150	
11	450	150		61	600	150		111	250	150		161	600	150		211	600	150	
12	600	150		62	600	150		112	600	150		162	600	150		212	600	150	
13	450	150		63	600	150		113	600	150		163	600	150		213	600	150	
14	450	150		64	600	150		114	600	150		164	600	150		214	600	150	
15	600	150		65	600	150		115	600	150		165	450	150		215	600	150	
16	600	150		66	600	150		116	600	150		166	250	150		216	600	150	
17	600	150		67	600	150		117	300	150		167	600	150		217	600	150	
18	600	150		68	600	150		118	600	150		168	600	150		218	600	150	
19	600	150		69	600	150		119	600	150		169	600	150		219	600	150	
20	600	150		70	600	150		120	600	150		170	600	150		220	600	150	
21	600	150		71	450	150		121	600	150		171	600	150		221	450	150	
22	600	150		72	600	150		122	600	150		172	300	150		222	250	150	
23	600	150		73	450	150		123	600	150		173	600	150		223	600	150	
24	600	150		74	450	150		124	600	150		174	600	150		224	600	150	
25	600	150		75	600	150		125	600	150		175	600	150		225	600	150	
26	450	150		76	600	150		126	600	150		176	600	150		226	600	150	
27	600	150		77	600	150		127	600	150		177	600	150		227	600	150	
28	450	150		78	600	150		128	600	150		178	600	150		228	300	150	
29	450	150		79	600	150		129	600	150		179	600	150		229	600	150	
30	600	150		80	600	150		130	600	150		180	600	150		230	600	150	
31	600	150		81	600	150		131	600	150		181	600	150		231	600	150	
32	600	150		82	600	150		132	600	150		182	600	150		232	600	150	
33	600	150		83	600	150		133	600	150		183	600	150		233	600	150	
34	600	150		84	600	150		134	600	150		184	600	150		234	600	150	
35	600	150		85	600	150		135	600	150		185	600	150		235	600	150	
36	600	150		86	450	150		136	600	150		186	600	150		236	600	150	
37	600	150		87	600	150		137	600	150		187	600	150		237	600	150	
38	600	150		88	450	150		138	600	150		188	450	150		238	600	150	
39	600	150		89	450	150		139	600	150		189	600	150		239	600	150	
40	600	150		90	600	150		140	600	150		190	600	150		240	600	150	
41	450	150		91	600	150		141	600	150		191	600	150		241	600	150	
42	600	150		92	600	150		142	450	150		192	600	150		242	600	150	
43	450	150		93	600	150		143	250	150		193	600	150		243	600	150	
44	450	150		94	600	150		144	600	150		194	600	150		244	450	150	
45	600	150		95	600	150		145	600	150		195	600	150		245	250	150	
46	600	150		96	600	150		146	600	150		196	600	150		246	600	150	
47	600	150		97	600	150		147	600	150		197	600	150		247	600	150	
48	600	150		98	600	150		148	600	150		198	600	150		248	600	150	
49	600	150		99	600	150		149	300	150		199	250	150		249	600	150	
50	600	150		100	600	150		150	600	150		200	600	150		250	600	150	

PS1	22 10 2021	FOR INFORMATION				CD	MC	MC
REV	DATE	DESCRIPTION				BT	CM	APP
DRAWING STATUS								
FOR INFORMATION								
CLIENT								
BASSETLAW HOSPITAL								
ARCHITECT								
PROJECT								
BASSETLAW HOSPITAL RAAC PANEL SURVEY								
TITLE								
RAAC PANEL SURVEY E D / THEATRES								
STATUS:	PROJECT No.	PROJECT	ORGANISATION	VALUERS/LEVEL	TYPE	DRAWING No.	REV	
S2	221-007	BLH -	AJP -	ZZ -	RF -	DR -	S - 0001	P01
SCALE & NO	DESIGNED	DRAWN	CD	CHECKED	APPROVED	DATE		
1:50	MC			MC	MC	OCT 2021		
 consulting engineers								
u/0121 227 1462 e/info@ajp.co.uk q1 Dale Street, Liverpool, L3 2ET								